

# SunRing™ Advanced Manufacturing and Field Deployment

Award #: SUB-2023-10314

HelioCon Workshop – July 12<sup>th</sup>, 2023

Presented by: Kyle Kattke (PI)

- SunRing heliostat was developed under SETO Drop-C project (DE-EE0008024) from 2017-2022
  - Total installed cost: \$96/m<sub>2</sub> at commercial scale (2019\$)
  - Wind criteria: 35 mph maximum tracking / 94 mph survival in stow
  - Total optical error (slope basis):
    - 1.6 mrad w/ FEA predicted structural deflection
    - 2.5 mrad w/ Photogrammetry measured structural deflection

**Baseline SunRing Prototype from Drop-C Project**



Baseline SunRing	
Reflective area	27 m <sup>2</sup>
Dimensions	8.46 x 3.21 m
Aspect ratio	2.6
Stow height	1.98 m
Mirror shape	Canted, flat
Foundation	3 x screw piles
Power	PV + battery
Control	Wireless


## HelioCon Project

- 24-month contract with 2 phases
- Overall goals
  - Move large portion of SunRing assembly offsite
  - Redesign mirror array and realize predicted optical performance
  - Reduce uncertainty in-field works (construction → commissioning)
  - Create holistic cost model (capital costs – lifetime O&M) in today's dollars

## Task 1: Offsite Assembly

- Azimuth drive and lower support structure pre-assembled offsite
  - Access to lower labor rates
  - Characterization of azimuth drive done in controlled environment
  - Assembly folds down to minimize shipping costs


**Pre-Assembles:**  
Blue – Main Lower Structure  
Red – Outer Space Frame



## Task 2: New Mirror Array Developed for Automated Assembly

- Develop automated assembly workstation for mirror array
  - Jig holds facets in ideal canted + focused position
  - Facets secured to torque tube to lock in optical shape
  - Adds 2-D focusing to SunRing at minimal cost
- Prototype to be built at SolarTAC facility (near Denver, CO)
  - SOFAST will be installed and used to tune jig to meet goal optical shape

**Mirror Array Assembly Workstation**



## Task 3: In-field Works

- Detailed workplan for all in-field work to reduce uncertainty in cost and schedule
  - SunRing installation in field
  - Solar field roads
  - Conceptual design and cost for rig to install all foundation piles simultaneously
  - Commissioning (controls + tracking calibration)

- Integration of workstation into automated assembly line

## Task 4: Holistic Heliostat Cost Model

- Update SunRing cost to current dollars
- Create cost model to capture all costs in heliostat lifecycle
  - Components, assembly, infrastructure, installation, commissioning, O&M
  - Will make publicly available